



June 7, 2022

Guidelines for contractors doing work in the Borough of Conneaut Lake. For any road openings to include waterline or sewer repair, the following specifications will need to be met:

- For any excavations, please follow OSHA guidelines for safety during excavation work.
- Any sewer or waterline that may be encased in concrete shall be repaired to original conditions.
- Backfill material shall consist of 2A Limestone or PennDOT certified material for roadwork.
- Compaction shall be done in 1' lifts and performed using either vibrator (plate or roller) compaction, a Sheeps foot roller may be used as long as dense compaction is met.
- Final grade shall consist of a minimum of 6" of Binder coarse (3/4") asphalt and shall have a finish grade as to meet and stay at finish grade. All edges will be sealed between new and old asphalt with certified crack sealant.
- Any temporary backfill to grade shall be with material listed above will be maintained by contractor until final asphalt grade is completed. Any temporary back fill will be removed and asphalted within a 30-day period.
- Any work that extends into the Borough Right-of-Way shall follow compaction rules listed above and restored to original material i.e. dirt, grass or gravel.

If there are any questions, please feel free to contact the Borough office or the Public Works Supervisor.

Jim Donnachie
Public Works Supervisor
Borough of Conneaut Lake

Email: Jimbo2854@gmail.com
Cell: 330-502-2854